

Integrated Geothermal District Heating & Cooling System for Utrecht, Netherlands

10.5 MWth

Heating

5.0 MWth

Cooling

€74/MWh

LCoE

TEAM GEOLOGIC ANALYTICS

Uadia Moses Imoukhedeh [SPE 5174626](#)

Ogundimu Samuel Oluwaseun [SPE 5408045](#)

Akanmu Oluwaseun Emmanuel [SPE 5436014](#)

Adejor Friday Emmanuel [SPE 5510461](#)

Favour Ifeanyichukwu Ogboi [SPE 5898562](#)

The Challenge & Our Central Insight

The brief demands a coherent system — not a single well — delivering firm heating and cooling, sustainably and economically, from a medium-temperature aquifer.



10 MWth Heating

From a low-enthalpy reservoir (70–77 °C).



5 MWth Cooling

Year-round, balanced seasonally.



Low-Carbon

Minimise fossil & grid electricity.



Flexibility

Bridge constant supply vs seasonal demand.




OUR CENTRAL INSIGHT

Transmissivity beats temperature.

For a low-enthalpy resource, the fluid volume the reservoir delivers matters more than how hot it is. A hot but tight well produces no usable power.

PKP-01: 88 °C but 0.1 Dm → not viable

From Raw Logs to a Bankable System




Engineering rigour and evaluation discipline come before architectural complexity — every parameter is traceable to data or the surface design report.

Data Engineering: Getting the Basics Right



Missing-data audit — -999.25 null sentinel detected & flagged



MD vs TVD — depth correction for the deviated well

Three quiet errors most teams will carry forward:

Caught a hidden null code

The -999.25 sentinel was mapped to true missing values before any statistics were computed.



Caught a labelling error

A ThermoGIS sheet headed “PKP-01” carried BLT-01 coordinates — flagged and corrected before screening.

Caught the depth trap

Target depths in along-hole MD were converted to TVD via the well-path survey — or every temperature estimate would be wrong.

Transmissivity Drives Viability



31.1 Dm

REINJ-01 — best in class

PKP-01


88 °C but 0.1 Dm → useless

Final Subsurface Architecture


Well	Role	Temp °C	Flow m³/h	Trans. Dm
BLT-01	Validated Production	77	105	9.3
GLA-01	Optimised Corridor	70	140	15.2
GLA-02	Backup / Contingency	71	132	13.4
REINJ-01	Reinjection Corridor	55	192	31.1

Production doublet: BLT-01 + GLA-01 deliver 245 m³/h of blended 73 °C brine. GLA-02 is held in reserve. REINJ-01 — the highest-injectivity corridor at 31.1 Dm — safely accepts the cooled brine and maintains reservoir pressure.

GLA-01 — ThermoGIS Evidence



System Architecture at a Glance



Thermodynamics of the Production Loop

BLT-01

77 °C · 105 m³/h

30.33 kg/s

+

GLA-01

70 °C · 140 m³/h

40.44 kg/s

BLENDED PRODUCTION

73 °C · 70.78 kg/s

Total geothermal power

$$Q = \dot{m} \cdot C_p \cdot \Delta T = 70.78 \times 4.0 \times (73 - 37.5)$$

$$Q \approx 10.05 \text{ MWth}$$

Geothermal

10.05 MWth



+ Heat pump

0.45 MWth



= Delivered

10.5 MWth



Honest engineering: geothermal supply (10.05 MWth) and the heat-pump upgrade (0.45 MWth) **together meet the 10.5 MWth heating target — comfortably above the 10 MW minimum.** The heat pump is the engineered bridge from a low-enthalpy aquifer to a usable district supply temperature.

Energy Centre, Storage & Renewable Integration



Titanium Heat Exchanger

Separates corrosive brine from the clean district loop.



Heat Pump (COP $\approx$ 2.25)

Upgrades 68 $\rightarrow$ 70 $^{\circ}$ C; +0.45 MWth on 0.2 MW electric.



ATES Seasonal Wells

Warm 15–35 $^{\circ}$ C, cold 8–15 $^{\circ}$ C — shifts heat & cold across seasons.



Buffer Tanks

Hot 575 m³/20 MWh + cold 1,225 m³/10 MWh shave 4-hr peaks.



Mechanical Chiller

5 MWth cooling at 7/15 $^{\circ}$ C; rejects to ATES cold well.




1.5 MW Solar PV


Covers all parasitic load (1.2 MW) — renewably self-sufficient.

Two-tier storage (seasonal ATES + daily buffer tanks) lets the wells run near-constant at their efficient point, decoupling continuous supply from seasonal demand.

Seasonal Demand & Annual Dispatch



Monthly heating & cooling demand vs capacity



Integrated monthly dispatch — geothermal + storage + minimal backup

>95 %

Demand met by geothermal + storage


10.5 MWth

Firm heating, every winter month

5.0 MWth

Firm cooling through summer peak

Capital Cost & Levelised Cost of Energy



CAPEX composition (left) and annual operating costs (right)

Depth-based drilling: each of 5 wells costed by its own depth — BLT-01 (1,700 m), GLA-01 (1,642 m), REINJ-01 (1,211 m), 2 ATES wells (150 m). Total drilling €25.5 M.

€41.0 M

Total capital expenditure


€74.4/MWh

Base-case LCoE (EU range)

€1.23 M/yr

Annual operating cost

Uncertainty: 10,000-Run Monte Carlo



Probabilistic LCoE distribution (10,000 simulations)

P10

€67

/MWh

P50


€80

/MWh

P90

€95

/MWh



Tornado sensitivity — ±20 % on each parameter

Why this matters: a single LCoE hides risk. Even at P90 the system stays within the EU district-heating range — robust, not just optimistic.

Limitations & Key Assumptions

We state our boundaries plainly — a credible design is one whose limits are understood.



Known Limitations

- **No coupled reservoir simulation** — steady-state flow assumed; thermal drawdown over time not modelled.
- **GLA-01 is a hypothetical target** — not an existing well — new drilling carries delivery uncertainty.
- **Simplified demand profiles** — no hourly district consumption data within the challenge framework.
- **ThermoGIS P50 used deterministically** — full probabilistic reservoir coupling not implemented.
- **ATES integration is conceptual** — no groundwater-flow simulation performed.



Key Assumptions

Brine properties: $\rho = 1040 \text{ kg/m}^3 \cdot C_p = 4.0 \text{ kJ/kg}\cdot\text{K}$

Reinjection temperature: 35–40 °C after heat extraction

District regime: 70 °C supply / 40 °C return

Heat pump COP: 2.25 (68→70 °C upgrade)

Economic lifetime: 15 years, 6 % discount rate

Demand basis: 10 MWth heat / 5 MWth cool (minimums)

Why This Submission Stands Out



Data-engineering rigour

TVD depth correction, hidden-null detection and a caught label error — quiet mistakes most teams carry forward.



True system integration

Geothermal + reinjection + heat pump + chiller + ATEs + buffer tanks + solar — a complete energy system, not a single well.



Uncertainty-aware economics

A full Monte Carlo risk profile (P10/P50/P90), not a single hopeful LCoE — the language investors trust.



Honest, defensible engineering

We state plainly that geothermal + heat pump together meet 10.5 MWth, framing the margin as deliberate efficient design.



Conclusions & Recommendations

Utrecht can be supplied with firm, low-carbon district heating and cooling from a low-enthalpy aquifer — delivered by rigorous data engineering, integrated thermal design, and economics that survive scrutiny under uncertainty.



Drill an appraisal well at GLA-01 — Convert the hypothetical corridor to a proven producer before final investment — the single biggest uncertainty.

10.5 / 5.0

MWth heat / cool



Acquire hourly demand data — Replace the simplified seasonal profile with metered consumption to refine storage sizing.

€74/MWh

Base-case LCoE



Run a coupled reservoir + ATEs model — Quantify thermal drawdown and groundwater interaction over the 30-year life.

>95 %

Geothermal share